SUBGRADE STABILIZATION AND PAVING OVERLAY FOR NH-150 FROM KM. 459.930 TO KM. 462.150 UNDER NATIONAL HIGHWAYS DIVISION NO-III FOR A LENGTH OF 2.20KM, IN THE STATE OF MANIPUR MANIPUR, INDIA



Pavement Stabilization

Client:	Products used & Quantity supplied:		
GOVERNMENT OF MANIPUR, PUBLIC WORKS DEPARTMENT	• TFI BIAXIAL GEOGRID TGB 30/20 - 66,000 SQM.		
Authority:	 TFI PP NONWOVEN TECHGEO PR 20 - 66,000 SQM TFI PAVING FABRIC TECHPAVE C040 - 30,800 SQM 		
MINISTRY OF TRANSPORT ; ATIRA			
Manufacturer & Supplier:	Year of construction:		
TECHFAB (INDIA) INDUSTRIES LTD.	2015		

Approach Length: 2.2 km

Project description:

The project was to expand the existing road from km 459.930 to km 462.150 on NH-150 along with other activities like construction of culverts, approach culverts and pucca drain. It was required to build a durable road over not so good foundation conditions. It was also required to restrict the percolation of water through pavement.

Solution:

Techfab (India) Industries Ltd submitted a proposal of using Geosynthetics to strengthen the pavement against heavy vehicular impacts & also restrict the percolation of water. For construction of such desired type of pavements, the various products as suggested below shall be used to cater the needs of high stresses developed by heavy vehicles.

- TechGeo PR series Nonwoven Geotextile is strong, flexible and dimensionally stable fabric structure, with optimum pore sizes and high permeability. TechGeo PR Geotextile can be used as a separator, filter & drainage purpose.
- TechGrid Geogrid TGB Series having with high tenacity, high tensile modulus, low creep and low shrinkage. The
 PVC coated grids shows a protective cover enhancing the dimensional stability of the geogrid, resistance to
 installation damage and protection from the environment act as an area stabilization & reinforcement for the
 granular road base & sub base.





Please find below the photographs for the execution of pavement with the proposed Geosynthetic materials under the guidance of site engineer:



Preparation of sub-base for Road Expansion



Preparation of subgrade for Road Expansion



Laying of Nonwoven Geotextile TechGeo PR20 Fabric on subgrade



Laying of Biaxial Geogrid TFI TGB 30/20 on Subgrade



Demonstration by Expert from ATIRA with Officials of PWD



Levelling and fixing of Geosynthetic material on Subgrade





Laying of GSB on Geosynthetic Material

Benefits of TechGeo Nonwoven Geotextile:

- Acts as a "Filter" by preventing the backfill material from being washed out through Gabion face.
- Acts as a "Separator" between the backfill material and the Gabion fascia and thereby prevents the mixing of the tow.

Advantage of Techgrid Geogrid Biaxial:

- Better Interlocking and load transfer, due to apertures and high interface frictional resistance between Geogrid and sand.
- It will minimize the differential settlement.

Benefits of Woven Geotextile –TFI 3000 Series

- It is used as a "basal reinforcement" of embankments on soft ground conditions.
- Act as a "Working Load Transfer Platform" to transfer vehicular/ impact loads deep into the soil safely.

		OOVERNP		OF BANFUR DEPARTMENT
		CONTRACTOR BURNE 200	1	UNDER THIONGON NO IK PAD, HAMPUR
WORK	WORK COMPLETION CERTIFICATE BLITING 2014		Purchase of Geolardia Materials for providing in the Purchase of Geolardia Materials for providing in the construction of load on NH-150 from line 428,530 to key construction biological Vigoways Givision No.16 for a	
5	t Name of Work		construction matter National Vighways General	
and and	-1		101	2,155 0 2 20 km.
	-		N	eckfab katia Industries Ltd. Murthai.
1	2	Job NO.	1.2	echiat Early rest
1	3	Name of Agency	1	SIL SALONGOUS
		Nominated Sub-Contractor	1	 StanCAMUL 2015-1042. dt. 22/09/2015
	4	Supply Order No.		Rs 91,82,801/-
	.5	Sanctioned Amount		Rs 91, Kr. How
	4			22.09.2013
F	1			51.12.2015
1	8	Actual Date of Completion	ĥ	31.12.2015
t		Actual Date of Contract Freeze	ESS.	100% Completed
1	10	Up to date Physicar		Ra 91,52,930'-
- 1	- 11	Tendered Cest	d the	Ra 91,82,800'-
	12	in date total value		
	Scal	of Work as por Agreement: - Supply of Gos-taxile material	s. ation !	it see and performance)-
		The contractor has not been	debar	nistery it any and performance)- red from any contract work. His record of performance is
		neral Remarks (Monitoring Usig The contractor has not been digitation)	debar	Signature of the Concerned Engineer in Charge
		The contractor has not been	debar	Signature of the Concerned Engineer in Charge
	5	The contractor has not been solded on the contractory	debar	Signature of the Concerned Engineer in Charge
	5	The contractor has not been solded on the contractory	debar	Signature of the Concerned Engineer in Charge
	5	The contractor has not been	debar	Signature of the Concerned Engineer in Charge

Completion Certificate from Department

Conclusion:

The project was successfully completed in 2015.

For further details kindly contact :

TechFab India Industries Ltd. 711/712, Embassy Centre, Nariman Point, Mumbai – 400021 Tel: + 91– 22 - 2287 6224 / 6225 Fax: + 91– 22 - 2287 6218 E: info@techfabindia.com W: www.techfabindia.com